Work Request: SP053196

Job Title: DONNYBROOK - BOYUP BROOK RD DONNYBROOK

Address: DONNYBROOK-KO ROAD DONNYBROO

Design Office: CCS Design Comm SVM

Construction Branch: South Country

Work Driver: COMMERCIAL / INDUSTRIAL FULL COST

Underlying Cause:

Work Type: Generic Full Cost

Quote Version: 1

Option:

Issue Date:

Approval:

Cost Summary

Cost Type	Internal Costs	External Costs	Customer Contribution (excl GST)
Compatible Units:	$76,805.81	$76,805.81	$76,805.81
Non Compatible Units:	$51.51	$51.51	$51.51
Quote Adjustment:	$0.00	$0.00	$0.00
Travel:	$0.00	$0.00	$0.00
Contingency:	$7,685.73	$7,685.73	$7,685.73
QA Charge	$0.00	$0.00	$0.00
Total:	**$84,543.05**	**$84,543.05**	**$84,543.05**
Less Subsidy:			$0.00
Customer Contribution (excl GST):			***$96,294.54***
GST Amount:			***$9,629.45***
Total Customer Contribution (incl GST):			***$105,923.99***

Cost Breakdown

Work Order	Hours	Internal Cost	External Cost
OVERHEAD CONSTRUCTION	83.58	$25,108.12	$25,108.12
UNDERGROUND CONSTRUCTION	19.95000	$29,645.55	$29,645.55
COMMISSIONING	4.360000	$800.14	$800.14
CUSTOMER SERVICE WORK	0	$40.67	$40.67
NON NETWORK WORK	11.46	$12,716.23	$12,716.23
SWITCHING	8.760000	$1,732.32	$1,732.32
TESTING	5.460000	$913.95	$913.95
WORK PACKAGING/PRELIM SITE INSPECTION	35	$5,900.35	$5,900.35
	168.57	**$76,857.32**	**$76,857.32**

Compatible Units

SCU Type	CU Name	CU Description	OT	Qty	Cable Allow Qty	Order Item	Int Chrg	Mat Only	Unit Internal Cost	Total Internal Cost	Opt B Chrg	Incl in EAC	Unit External Cost	% Chrg	Customer Contribution (excl GST)
	AUX_002	Update GIS / asset data for minor job	N	1		Y	Y	N	$121.42	$121.42			$121.42	100	$121.42
	AUX_004	Package work for contractors per hour	N	3		Y	Y	N	$109.36	$328.09			$109.36	100	$328.10
	AUX_005	Manage customer project per hour	N	32		Y	Y	N	$174.13	$5,572.26			$174.13	100	$5,572.26
	AUX_007	Notify customers of work in vicinity	N	1		Y	Y	N	$178.68	$178.68			$178.68	100	$178.68
	AUX_011	Minor Adm for internal underground C	N	1		Y	Y	N	$89.84	$89.84			$89.84	100	$89.84
	AUX_013	Cust Driven Resource Management -	N	3		Y	Y	N	$608.47	$1,825.42			$608.47	100	$1,825.42
	AUX_014	Cust Driven Resource Management -	N	1		Y	Y	N	$572.16	$572.16			$572.16	100	$572.16
	CABLE_05	Lay XLPE LV cable 10/16/25mm	N	45		Y	Y	N	$5.75	$258.75			$5.75	100	$258.75
	CABLE_07	Lay cable protection covers	N	8		Y	Y	N	$30.69	$245.48			$30.69	100	$245.48
	CABLE_14	Haul XLPE LV cable 10/16/25mm	N	125		Y	Y	N	$16.91	$2,113.54			$16.91	100	$2,113.54
	CN41	Cable 16mm2 XLPE streetlight	N	145	8	Y	Y	N	$10.99	$1,593.63			$10.99	100	$1,593.63
	CN42	Cable 25mm2 XLPE LV	N	20	1	Y	Y	N	$31.43	$628.55			$31.43	100	$628.55
	CN52_7/475	Conductor AAAC 7/4.75	N	70		Y	Y	N	$3.73	$260.90			$3.73	100	$260.90
	CN54	Plastic slabs 2.1m long	N	4		Y	Y	N	$18.45	$73.79			$18.45	100	$73.79
	CN73_LV10/16	End cap push on 10/16mm2 streetligh	N	5		Y	Y	N	$1.73	$8.63			$1.73	100	$8.63
	CN73_LV25	End cap push on 25mm2 3C screene	N	3		Y	Y	N	$3.87	$11.60			$3.87	100	$11.60
	CN9_7/475AA	PG clamp Al to Al 7/4.75	N	6		Y	Y	N	$10.00	$60.00			$10.00	100	$60.00
	DDRILL_05	Install poly pipe 63mm: Soil/Clay	N	125		Y	Y	N	$120.58	$15,072.19			$120.58	100	$15,072.19

GENSER_07	Apply for local authority permits	N	1		Y	Y	N	$31.32	$31.32	$31.32	100	$31.32
HV30_N	RDA/Tee-off 1PH medium	N	2		Y	Y	N	$87.94	$175.88	$87.94	100	$175.88
HV34_PT	Pole Top Earthing - Base Kit	N	1		Y	Y	N	$82.76	$82.76	$82.76	100	$82.76
HV34_PT12	Pole Top Earthing - 12mm Addon	N	1		Y	Y	N	$41.80	$41.80	$41.80	100	$41.80
HV34_PTS	Pole Top Earthing - Stay Addon	N	1		Y	Y	N	$51.27	$51.27	$51.27	100	$51.27
HV52_3FT	DOF fault tamer 3A	N	1		Y	Y	N	$1,392.84	$1,392.84	$1,392.84	100	$1,392.84
LOCATE_01	Locate 1 or 2 UG services: Sand/Soil	N	125		Y	Y	N	$6.33	$790.63	$6.32	100	$790.63
LU10	Mini pillar & 1x25mm2 cable terminati	N	1		Y	Y	N	$334.66	$334.66	$334.66	100	$334.66
LU61_25_240O	OH Pole to pillar 25mm2 Cu cable 24	N	1		Y	Y	N	$118.87	$118.87	$118.87	100	$118.87
LU61_25_240U	UG Pole to pillar 25mm2 Cu cable 24	N	1		Y	Y	N	$25.84	$25.84	$25.84	100	$25.84
OH INST_001	Install Wood pole: Clay / normal soil	N	1		Y	Y	N	$637.18	$637.18	$637.18	100	$637.18
OH INST_001A	Install Lamp Std: Clay/normal soil	N	2		Y	Y	N	$2,218.39	$4,436.78	$2,218.39	100	$4,436.78
OH INST_004	INST intermediate cross arm or 1 PH	N	4		Y	Y	N	$387.28	$1,549.11	$387.28	100	$1,549.11
OH INST_007	Install conductor incl. straining	N	2		Y	Y	N	$197.47	$394.94	$197.47	100	$394.94
OH INST_009	Install 1 PH transformer	N	1		Y	Y	N	$1,277.64	$1,277.64	$1,277.64	100	$1,277.64
OH INST_016	Install 1 PH Drop-Out-Fuse	N	1		Y	Y	N	$1,277.64	$1,277.64	$1,277.64	100	$1,277.64
OH INST_024	Install ground / aerial / outrigger stay	N	1		Y	Y	N	$542.17	$542.17	$542.17	100	$542.17
OH INST_033	Install taps/tails/joints	N	4		Y	Y	N	$968.43	$3,873.73	$968.43	100	$3,873.73
OH RELO_025	Relocate minor pole / pole top items	N	2		Y	Y	N	$583.95	$1,167.91	$583.95	100	$1,167.91
PO8_R	PWOD Rural 12.5m 6kN painted	N	1		Y	Y	N	$1,627.67	$1,627.67	$1,627.67	100	$1,627.67
PRJMAN_01	Conduct prestart meeting	N	1		Y	Y	N	$242.65	$242.65	$242.65	100	$242.65
RE3_7/475AA	Running earth termination 7/475 AAC/	N	2		Y	Y	N	$37.37	$74.75	$37.37	100	$74.75
REMRES_17	Remove & restore established lawn	N	10		Y	Y	N	$23.26	$232.59	$23.26	100	$232.59
SL11_6L	SNGL OUTRCH Steel STD 12.5M 170	N	2		Y	Y	N	$2,808.93	$5,617.86	$2,808.93	100	$5,617.86
ST1_19/200W	Ground stay 19/2.00 PWOD screw an	N	1		Y	Y	N	$350.88	$350.88	$350.88	100	$350.88
SWITCH_OH004	Major O/H HV switching with transfor	N	3		Y	Y	N	$577.44	$1,732.32	$577.44	100	$1,732.32
TESTCOM_001	Test & commission O/H assets per ho	N	1		Y	Y	N	$370.97	$370.97	$370.97	100	$370.97
TESTCOM_002	Test & commission U/G assets per ho	N	1		Y	Y	N	$429.16	$429.16	$429.16	100	$429.16
TESTCOM_007	Test LV cables: Brown field	N	3		Y	Y	N	$304.65	$913.95	$304.65	100	$913.95
TRAFFIC_01	SITE VISIT	N	1		Y	Y	N	$164.97	$164.97	$164.97	100	$164.97
TRAFFIC_02	Traffic Control Drawing "Site Specific"	N	1		Y	Y	N	$213.61	$213.61	$213.61	100	$213.61
TRAFFIC_05	COMPLEX WORKS TRAFFIC MANA	N	1		Y	Y	N	$1,461.69	$1,461.69	$1,461.69	100	$1,461.69
TRAFFIC_07	1 X TRAFFIC CONTROLLER, 1 X VE	N	24		Y	Y	N	$105.36	$2,528.64	$105.36	100	$2,528.64
TRAFFIC_08	2 X TRAFFIC CONTROLLER, 1 X VE	N	24		Y	Y	N	$182.81	$4,387.44	$182.81	100	$4,387.44

TRAFFIC_09	FLASHING ARROW BOARD	N	1		Y	Y	N	$126.86	$126.86		$126.86	100	$126.86
TRAFFIC_10	ELECTRONIC VARIABLE MESSAGE	N	1		Y	Y	N	$253.00	$253.00		$253.00	100	$253.00
TRAV OH_004	2 person O/H crew type 1: DXLP + DX	N	64		Y	Y	N	$9.22	$590.28		$9.22	100	$590.28
TRAV OH_007	Switching crew: DCOM	N	192		Y	Y	N	$4.17	$801.27		$4.17	100	$801.27
TRAV UG_004	2 person U/G crew type 2: DCJN + DE	N	64		Y	Y	N	$7.83	$501.35		$7.83	100	$501.35
TRENCH_01	Excavate & fill by hand 450mm: Soil	N	10		Y	Y	N	$45.64	$456.38		$45.64	100	$456.38
TX5_25/12.7	TX 1PH 25kVA/12.7kV w/1 bushing 2	N	1		Y	Y	N	$3,836.47	$3,836.47		$3,836.47	100	$3,836.47
UG INST_009	Install mini pillar	N	1		Y	Y	N	$334.69	$334.69		$334.69	100	$334.69
UG INST_025	Red Spot Fuse Installation	N	1		Y	Y	N	$209.39	$209.39		$209.39	100	$209.39
UG JNT_006A	TERM LV cable to POLE or GRND M	N	5		Y	Y	N	$417.68	$2,088.40		$417.68	100	$2,088.40
UM3_R	Install red spot & fit fuse	N	1		Y	Y	N	$40.67	$40.67		$40.67	100	$40.67
									$76,805.81				**$76,805.81**

Non Compatible Unit Items

Description	Work Order	Work Order Task	Total Internal Cost	Opt B Chrg	Include in EAC	Total Corporate Cost	% Chrg	Customer Contribution (excl GST)
GF1947x1, FE0112x2	OVERHEAD CONSTRUCTIO	O/H STREETLIGHT INSTALLATION O	$51.51			$51.51	100	$51.51
			$51.51			**$51.51**		**$51.51**

******* End of Report *******